

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31096/CALL-4

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2019-20, Date: 30.11.2019

Construction of drain and improvements of culverts at Hebbala sarovara layout in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				SHIVAKUMAR N M ()		
				In Figures		In Words
1	576.54	KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications Specification No.KBS 2.1(b)/2.3.5 PWD SR 2016-17 (P-5, It,-2.3)	Cum	86.0	49582.44	Rupees Eighty Six Only
2	4.5	KSRRB M 200-12.1. Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable materail with all lifts complete as per specifications (page No. 137, item No. 18.17)	Cum	327.0	1471.50	Rupees Three Hundred Twenty Seven Only
3	6.48	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m. (P-258,It.37.48)	Cum	182.0	1179.36	Rupees One Hundred Eighty Two Only
4	100.14	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.3)	Cum	5159.0	516622.26	Rupees Five Thousand One Hundred Fifty Nine Only
5	6.48	Reconstruction of size stone masonry with available stones in C.M 1:6 as per direction of the Engineer-in-charge.	Cum	2701.0	17502.48	Rupees Two Thousand Seven Hundred One Only
6	1.62	KSRB 5.2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high, bond stones at two m, apart in each course including cost of materials, labour, curing complete as per specifications. PWD SR 2015-16 (P-23, It5.6)	Cum	4521.0	7324.02	Rupees Four Thousand Five Hundred Twenty One Only
7	187.97	KSRB 4.2.2:Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.6 PWD SR 2016-17 (P-13, It.4.11)	Cum	6371.0	1197556.87	Rupees Six Thousand Three Hundred Seventy One Only
8	9.4	KSRB 4.9-1:Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No.KBS 4.6.3 PWD SR 2016-17 (P-17, It.4.46.2)	Tonne	64243.0	603884.20	Rupees Sixty Four Thousand Two Hundred Forty Three Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				SHIVAKUMAR N M ()		
				In Figures		In Words
9	1454.4	KSRB 4-6.4:Providing and removing centering, shuttering, strutting propping etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No.KBS 4.6.2 PWD SR 2016-17 (P-15, It.4.31)	Sqm	400.0	581760.00	Rupees Four Hundred Only
10	380.1	Providing and fixing 10 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specification (Data Rate Approved)	Sqm	1200.0	456120.00	Rupees One Thousand Two Hundred Only
11	19.53	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and line aggregates @ 0.459 cum,machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.6)	Cum	5767.0	112629.51	Rupees Five Thousand Seven Hundred Sixty Seven Only
12	22.5	Providing and fixing 25 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specification (Data Rate Approved)	Sqm	3000.0	67500.00	Rupees Three Thousand Only
13	576.54	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 PWD SR 2013-14 (P-144 & 133, It.No. 17.1)	Cum	106.0	61113.24	Rupees One Hundred Six Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/10/1